

## NOTES:

- 1. WHERE AN EXTERNAL CHECK VALVE IS REQUIRED BY THE PUMP MANUFACTURER, THE PRESSURE LINE TEST TEE MUST BE LOCATED BETWEEN THE CHECK VALVE AND THE PUMP STATION.
- 2. 7' MINIMUM COVER FOR PRESSURE LATERALS LOCATED UNDER AREAS THAT MAY BE CLEARED OF SNOW AND HAVE VEHICULAR TRAFFIC.



TYPICAL EXTERIOR PUMP STATION INSTALLATION

STANDARD DETAIL

LAT-09

Revision Date: 2/2/23