



# Snyderville Basin Water Reclamation District

SNYDERVILLE BASIN WATER RECLAMATION DISTRICT  
PARK CITY, UTAH


EAST CANYON WRF 2026 PREPURCHASE  
DESIGN AND CONSTRUCTION MANAGEMENT SERVICES

PROJECT NO. 204825

ADDENDUM NO. 1  
TO THE  
CONTRACT DOCUMENTS

APRIL 29, 2026

Digitally signed by Erin R. Andersen  
Contact Info: Carollo Engineers, Inc.  
Date: 2026.04.29 10:59:06'00'



Bidders on the above-named project are hereby notified that the Bidding Documents are modified as indicated below. Bidders are required to acknowledge receipt of this Addendum in the space provided on Document 00410 - Bid Form.

This Addendum shall become part of the Contract and provisions of the Contract apply.

## **SPECIFICATIONS**

The following sections are modified as indicated below.

1. SECTION 16990 - CONDUIT SCHEDULE:
  - a. ADD attached section in its entirety.

## **DRAWINGS**

The following drawings are modified as indicated below.

1. DRAWING 77M03:
  - a. Add new keynote 10 pointing to the existing steel support frame near the edge of the new polymer blending unit on Plan C:
    - 1) "Modify existing steel support frame to accommodate new anchor points for new polymer blending skids per manufacturer's approved shop drawings. New steel and welded/bolted connections shall conform to AISC 360 and AWS D1.1. New steel members shall match grade and finish of existing frame. Contractor shall submit proposed modifications, including connection details and welding procedures, for review prior to fabrication."

## SECTION 16990A

### CONDUIT SCHEDULE

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. Conduit requirements:
  - 1. As defined in Section 16050 and Section 16130.
  
- B. Cable requirements and definitions:
  - 1. As defined in Section 16050 and Section 16123.
  - 2. 2/CS#16: 2 conductor, 16 gauge, twisted shielded pair.
  - 3. \*/C#Y: Multiconductor cable (\* indicates number of conductors, Y indicates conductor size and insulation).
  - 4. CAT6: Category 6 Ethernet cable.
  - 5. MFR: Manufacturer or vendor furnished cable.
  - 6. VFD: Shielded VFD cable with integral ground.

#### PART 2 PRODUCTS

Not Used.

#### PART 3 EXECUTION

##### 3.01 CONDUIT SCHEDULE

- A. Conduit Schedule is presented on the following pages.

# CONDUIT SCHEDULE AREA

SNYDERVILLE BASIN WRD 2026 PREPURCHASE PROJECT

ENGINEER

JRS

REVISION

DATE

4/29/26

CONDUIT			CONDUCTORS			GROUND			DESCRIPTION	CONNECTING SEGMENTS
NUMBER	DWG	SIZE	#	SIZE	TYPE	#	SIZE	TYPE		
C-50-100	50E01	0.75"	2	#14	XHHW-2	1	#14	XHHW-2	FR: CONDUIT TEE TO: LCP-CP-14 2 #14 >> TSH-CP-14 CONTROL	
C-50-101	50E01 50E02	0.75"	10	#14	XHHW-2	1	#14	XHHW-2	FR: LCP-CP-14 TO: VFD-CP-14 8 #14 >> LCP-CP-14 CONTROL 2 #14 >> TSH-CP-14 CONTROL	
C-50-105		0.75"	2	#14	XHHW-2	1	#14	XHHW-2	FR: CONDUIT TEE TO: LCP-CP-15 2 #14 >> TSH-CP-15 CONTROL	
C-50-106	50E01 50E02	0.75"	10	#14	XHHW-2	1	#14	XHHW-2	FR: LCP-CP-15 TO: VFD-CP-15 8 #14 >> LCP-CP-15 CONTROL 2 #14 >> TSH-CP-15 CONTROL	
C-50-110	50E01	0.75"	2	#14	XHHW-2	1	#14	XHHW-2	FR: CONDUIT TEE TO: LCP-CP-16 2 #14 >> TSH-CP-16 CONTROL	
C-50-111	50E01 50E02	0.75"	10	#14	XHHW-2	1	#14	XHHW-2	FR: LCP-CP-16 TO: VFD-CP-16 8 #14 >> LCP-CP-16 CONTROL 2 #14 >> TSH-CP-16 CONTROL	
C-50-150	50E02	1"	12	#14	XHHW-2	1	#14	XHHW-2	FR: VFD-CP-16 TO: CONDUIT TEE 10 #14 >> VFD-CP-16 CONTROL 2 #14 >> LOW LEVEL INTERLOCK	C-50-152
C-50-151	50E02	1"	12	#14	XHHW-2	1	#14	XHHW-2	FR: VFD-CP-15 TO: CONDUIT TEE 10 #14 >> VFD-CP-15 CONTROL 2 #14 >> LOW LEVEL INTERLOCK	C-50-152
C-50-152	50E02	1.5"	24	#14	XHHW-2	1	#14	XHHW-2	FR: CONDUIT TEE TO: CONDUIT TEE 10 #14 >> VFD-CP-16 CONTROL 2 #14 >> LOW LEVEL INTERLOCK 10 #14 >> VFD-CP-15 CONTROL 2 #14 >> LOW LEVEL INTERLOCK	C-50-154 C-50-150 C-50-151 C-50-151
C-50-153	50E02	1"	12	#14	XHHW-2	1	#14	XHHW-2	FR: VFD-CP-14 TO: CONDUIT TEE 10 #14 >> VFD-CP-14 CONTROL 2 #14 >> LOW LEVEL INTERLOCK	C-50-154
C-50-154	50E02	1.5"	36	#14	XHHW-2	1	#14	XHHW-2	FR: CONDUIT TEE TO: PCM-CPB 10 #14 >> VFD-CP-16 CONTROL 2 #14 >> LOW LEVEL INTERLOCK 10 #14 >> VFD-CP-15 CONTROL 2 #14 >> LOW LEVEL INTERLOCK 10 #14 >> VFD-CP-14 CONTROL 2 #14 >> LOW LEVEL INTERLOCK	C-50-152 C-50-152 C-50-152 C-50-152 C-50-153 C-50-153
L-50-100	50E02	0.75"	3	#12	XHHW-2	1	#12	XHHW-2	FR: OUTDOOR AC COMPRESSOR UNIT TO: PANEL LPD 3 #12 >> ELEC ROOM HVAC UNIT POWER	
L-50-101		0.75"	1	MFR	CABLE	1	#14	XHHW-2	FR: INDOOR AC UNIT TO: OUTDOOR AC COMPRESSOR UNIT 1 MFR >> AC UNIT POWER	
N-50-150	50E02	0.75"	1		CAT6	1	#14	XHHW-2	FR: VFD-CP-16 TO: CONDUIT TEE 1 CAT6 >> VFD-CP-16 NETWORK	N-50-152
N-50-151	50E02	0.75"	1		CAT6	1	#14	XHHW-2	FR: VFD-CP-15 TO: CONDUIT TEE 1 CAT6 >> VFD-CP-15 NETWORK	N-50-152
N-50-152	50E02	1"	2		CAT6	1	#14	XHHW-2	FR: CONDUIT TEE TO: CONDUIT TEE 1 CAT6 >> VFD-CP-16 NETWORK 1 CAT6 >> VFD-CP-15 NETWORK	N-50-154 N-50-150 N-50-151
N-50-153	50E02	0.75"	1		CAT6	1	#14	XHHW-2	FR: VFD-CP-14 TO: CONDUIT TEE 1 CAT6 >> VFD-CP-14 NETWORK	N-50-154

# CONDUIT SCHEDULE AREA

SNYDERVILLE BASIN WRD 2026 PREPURCHASE PROJECT

ENGINEER

JRS

REVISION

DATE

4/29/26

CONDUIT			CONDUCTORS			GROUND			DESCRIPTION	CONNECTING SEGMENTS
NUMBER	DWG	SIZE	#	SIZE	TYPE	#	SIZE	TYPE		
N-50-154	50E02	1"	3		CAT6	1	#14	XHHW-2	FR: CONDUIT TEE TO: PCM-CPB 1 CAT6 >> VFD-CP-16 NETWORK 1 CAT6 >> VFD-CP-15 NETWORK 1 CAT6 >> VFD-CP-14 NETWORK	N-50-152 N-50-152 N-50-153
P-50-100	50E01	1.5"	1 2	3/C-#8:VFD #14	VFD XHHW-2			INTEGRAL	FR: P-CP-14 TO: CONDUIT TEE 1 3/C-#8:VFD >> P-CP-14 POWER 2 #14 >> TSH-CP-14 CONTROL	
P-50-101	50E01 50E02	1.5"	1	3/C-#8:VFD	VFD			INTEGRAL	FR: CONDUIT TEE TO: VFD-CP-14 1 3/C-#8:VFD >> P-CP-14 POWER	
P-50-102	50E02	1"	3	#6	XHHW-2	1	#10	XHHW-2	FR: VFD-CP-14 TO: MCC-D 3 #6 >> VFD-CP-14 POWER	
P-50-105	50E01	1.5"	1 2	3/C-#8:VFD #14	VFD XHHW-2			INTEGRAL	FR: P-CP-15 TO: CONDUIT TEE 1 3/C-#8:VFD >> P-CP-15 POWER 2 #14 >> TSH-CP-15 CONTROL	
P-50-106	50E01 50E02	1.5"	1	3/C-#8:VFD	VFD			INTEGRAL	FR: CONDUIT TEE TO: VFD-CP-15 1 3/C-#8:VFD >> P-CP-15 POWER	
P-50-107	50E02	1"	3	#6	XHHW-2	1	#10	XHHW-2	FR: VFD-CP-15 TO: MCC-D 3 #6 >> VFD-CP-15 POWER	
P-50-110	50E01	1.5"	1 2	3/C-#6:VFD #14	VFD XHHW-2			INTEGRAL	FR: P-CP-16 TO: CONDUIT TEE 1 3/C-#6:VFD >> P-CP-16 POWER 2 #14 >> TSH-CP-16 CONTROL	
P-50-111	50E01 50E02	1.5"	1	3/C-#6:VFD	VFD			INTEGRAL	FR: CONDUIT TEE TO: VFD-CP-16 1 3/C-#6:VFD >> P-CP-16 POWER	
P-50-112	50E02	1"	3	#4	XHHW-2	1	#8	XHHW-2	FR: VFD-CP-16 TO: MCC-D 3 #4 >> VFD-CP-16 POWER	
S-50-100		0.75"	1	MFR	CABLE	1	#14	XHHW-2	FR: THERMOSTAT TO: INDOOR AC UNIT 1 MFR >> THERMOSTAT SIGNAL	
S-50-150	50E02	0.75"	2	2/CS-#16		1	#14	XHHW-2	FR: VFD-CP-16 TO: CONDUIT TEE 2 2/CS-#16 >> VFD-CP-16 SIGNAL	S-50-152
S-50-151	50E02	0.75"	2	2/CS-#16		1	#14	XHHW-2	FR: VFD-CP-15 TO: CONDUIT TEE 2 2/CS-#16 >> VFD-CP-15 SIGNAL	S-50-152
S-50-152	50E02	1"	4	2/CS-#16		1	#14	XHHW-2	FR: CONDUIT TEE TO: CONDUIT TEE 2 2/CS-#16 >> VFD-CP-16 SIGNAL 2 2/CS-#16 >> VFD-CP-15 SIGNAL	S-50-154 S-50-150 S-50-151
S-50-153	50E02	0.75"	2	2/CS-#16		1	#14	XHHW-2	FR: VFD-CP-14 TO: CONDUIT TEE 2 2/CS-#16 >> VFD-CP-14 SIGNAL	S-50-154
S-50-154	50E02	1.5"	6	2/CS-#16		1	#14	XHHW-2	FR: CONDUIT TEE TO: PCM-CPB 2 2/CS-#16 >> VFD-CP-16 SIGNAL 2 2/CS-#16 >> VFD-CP-15 SIGNAL 2 2/CS-#16 >> VFD-CP-14 SIGNAL	S-50-152 S-50-152 S-50-153
C-77-100	77E01	0.75"	10	#14	XHHW-2	1	#14	XHHW-2	FR: VCP-SP-5 TO: CONDUIT TEE 10 #14 >> VCP-SP-5 CONTROL	C-77-102
C-77-101	77E01	0.75"	10	#14	XHHW-2	1	#14	XHHW-2	FR: VCP-SP-6 TO: CONDUIT TEE 10 #14 >> VCP-SP-6 CONTROL	C-77-102

# CONDUIT SCHEDULE AREA

SNYDERVILLE BASIN WRD 2026 PREPURCHASE PROJECT

ENGINEER

JRS

REVISION

DATE

4/29/26

CONDUIT			CONDUCTORS			GROUND				
NUMBER	DWG	SIZE	#	SIZE	TYPE	#	SIZE	TYPE	DESCRIPTION	CONNECTING SEGMENTS
C-77-102	77E01 77E02	1.5"	20	#14	XHHW-2	1	#14	XHHW-2	FR: CONDUIT TEE TO: PLC-200 10 #14 >> VCP-SP-5 CONTROL 10 #14 >> VCP-SP-6 CONTROL	C-77-100 C-77-101
L-77-100	77E01	0.75"	2	#10	XHHW-2	1	#10	XHHW-2	FR: VCP-SP-5 TO: CONDUIT TEE 2 #10 >> VCP-SP-5 POWER	L-77-102
L-77-101	77E01	0.75"	2	#10	XHHW-2	1	#10	XHHW-2	FR: VCP-SP-6 TO: CONDUIT TEE 2 #10 >> VCP-SP-6 POWER	L-77-102
L-77-102	77E01 77E02	0.75"	4	#10	XHHW-2	1	#10	XHHW-2	FR: CONDUIT TEE TO: LP-S 2 #10 >> VCP-SP-5 POWER 2 #10 >> VCP-SP-6 POWER	L-77-100 L-77-101
S-77-100	77E01	1"	3	2/CS-#16		1	#14	XHHW-2	FR: VCP-SP-5 TO: CONDUIT TEE 3 2/CS-#16 >> VCP-SP-5 SIGNAL	S-77-102
S-77-101	77E01	1"	3	2/CS-#16		1	#14	XHHW-2	FR: VCP-SP-6 TO: CONDUIT TEE 3 2/CS-#16 >> VCP-SP-6 SIGNAL	S-77-102
S-77-102	77E01 77E02	1.5"	6	2/CS-#16		1	#14	XHHW-2	FR: CONDUIT TEE TO: PLC-200 3 2/CS-#16 >> VCP-SP-5 SIGNAL 3 2/CS-#16 >> VCP-SP-6 SIGNAL	S-77-100 S-77-101

END OF CONDUIT SCHEDULE

END OF SECTION